


Section "AA"

LEGEND :


- |  |  |
|--|--|
| 1 Custom orb 26 guage corrugated steel deck  | 19 Window wall 2450 high. refer to window schedule.                            |
| 2 75x50 hwd battens at 850 crs. max.   | 20 Layout brickwork containing dpc's etc.                                      |
| 3 50mm thick rolled fibreglass insulation and double sided insulation.                               | 21 Interior brick paving.  |
| 4 19 mm T & G pine lining  | 22 25 mm min mortar bed.   |
| 5 Oregon millsawn truss as specified by engineer.  | 23 Waterproof membrane   |
| 6 Clerestory - refer to window schedule  | 24 50mm min packing sand.  |
| 7 300x75 concealed box gutter & flashing   | 25 525x350 footing with 6 strands of F8 trench mesh top & bottom with R6 ligs. |
| 8 350x50 millsawn oregon fascia.   | 26 200x200 min millsawn verandah posts.  |
| 9 10mm ceramic pipes as fixed ventilation.   | 27 400 square x 400 deep isolated pad footing under verandah posts.            |
| 10 Flashing around chimney.  | 28 External brick paving, to fall away from building.                          |
| 11 250x125 jarrah or redgum lintel over doors & windows.   | 29 specified shower.   |
| 12 Timber posts 200 x 200 min, except where truss is supported in corners of room to be 250x200 min. | 30 Brick on edge sill, & flashing under  |
| 13 900 x 600 slate shelf with 200mm set into wall.   | 31 Pine lining under eaves.  |
| 14 250 x 75 min jarrah or redgum lintel over interior doors in mud brick walls.                      | 32 200 x 30 oregon trim in corner of fireplace & ceiling                       |
| 15 Interior door. 2,040 high.  |  |
| 16 200x75 millsawn oregon rafters  |  |
| 17 Flashing under clerestory   |  |
| 18 200x75 millsawn oregon packers  |  |




Beam Layout.

--- Truss  
 --- 200 x 75 rafters  
 --- battens

NOTE - all adobe walls supporting rafters are to be load bearing.



Detail "a"



Section "BB"

SCOTT HOUSE - PAKENHAM  
Details

ALISTAIR KNOX & ASSOCIATES  
mt Pleasant rd, Eltham, (03) 439 7404

Scale - 1:50 1:20 1:100 / Date - march 84 /  
Drawn - danny

Job N<sup>o</sup> 1213

sheet 2 of 3