



LEGEND

- f fixed glazing.
- d glass door.
- c casement.
- p posts.
- cross on elevation indicates flywire screen.
- shading on plans & elevations indicate adobe brickwork.
- spray under floor for termites, etc., as per council regulations.
- down pipe positions shown on site plan.
- tc top hung casement.



LEGEND :

- 1 custom orb, 26 gauge, corrugated iron.
- 2 75 x 50 hwd battens at 800 crs.
- 3 50 mm thick, rolled fibreglass insulation with sisilation.
- 4 19 mm selected timber lining.
- 5 175 x 75 millsawn hardwood rafters.
- 6 350 x 50 millsawn hardwood fascia.
- 7 300 x 75 concealed box gutter.
- 8 capping.
- 9 selected timber posts, min 200 x 200 section.
- 10 loadbearing stud wall with selected timber lining.
- 11 200 x 50 millsawn hardwood packers.
- 12 specified windows.
- 13 brick or terracotta tile, sill.
- 14 100 x 250 on flat, hardwood lintel over doors in rooms 1, 3, 4 & 5. Jambes to match windows - ex 150 x 75.
- 15 specified internal doors.
- 16 layout brickwork containing dpc's, etc.
- 17 internal brick paving.
- 18 25 mm min mortar bed - waterproof.
- 19 waterproof membrane.
- 20 50 mm bed of packing sand.
- 21 525 x 350 footing with 2 layers of F.11 trenchmesh (top & bottom).
- 22 400 x 400 square isolated pad footing under verandah poles.
- 23 selected timber verandah poles, 150 x 150 min section.
- 24 external brick paving, to fall away from building.
- 25 specified bathroom benches.
- 26 specified clearstory lighting.
- 27 selected timber lining, internal & external.
- 28 300 x 100 millsawn oregon or hardwood ridge. (not over lobby).

SHEPPARTON T.A.F.E.
STUDENT HOSTEL

design Alistair Knox & associates
mt Pleasant rd, Eltham. 439 7404.

scale - 1:100, 1:50
date - july 84
drawn-danny

Job No 1224

sheet 2 of 9